

Superconducting Cavity Development at FNAL

P.Bauer, L.Bellantoni, T.Berenc, S.Bhashyam, C.Boffo,
R.Carcagno, C.Darve, B.DeGraff, I.Gonin, H.Edwards,
L.Elementi, M.Foley, T.Khabibouline, M.Kuchnir,
D.Mitchell, T.Nicol, J.Reid, A.Rowe, N.Solyak, B.Soyars,
I.Terechkine,

W.D.Möller, R.Wanzenberg, ... (DESY)

Nikolay Solyak

Fermilab Accelerator Advisory Committee

10-11 May 2004


Two 3.9GHz Designs

TM₁₁₀ mode *"CKM"*

K⁺ RF separator for K⁺ → πνν̄

Bunch profile measurement at zero crossing

$$B_{\text{MAX}} = 80\text{mT} \quad E_{\text{MAX}} = 18.6\text{MV/m}$$
$$L_{\text{eff}} = 0.5\text{m}, P_{\perp} = 5\text{ MV/m}$$



$$E_{\text{ACC}} = 14\text{MV/m}$$


$$B_{\text{MAX}} = 68\text{ mT} \quad E_{\text{MAX}} = 31.6\text{MV/m}$$

$$L_{\text{eff}} = 0.346\text{m}$$

TM₀₁₀ mode
"3rd Harmonic"


Linearize energy distribution within bunch before compression for better emittance

3rd Harmonic cavity to Improve Beam Characteristics in injector




Use of TM_{110} cavity in TESLA bunch compression reduces energy loss and a 2-stage system could permit compression to $< 300 \mu\text{m}$, reducing the "banana effect" - Piot & Decker, FNAL TM-2235

RF Design




- Basic electromagnetic design done with MAFIA, HFSS, MWS, lumped equivalent element methods
- Interface to mechanical FEMs (ANSYS, IDEAS) custom built



Lorentz force detuning




- ✓ CKM cavity: calculated $\Delta f = 770\text{Hz}$ for 1.6mm thick wall with free ends; measured at $\Delta f = 728\text{Hz}$.
- ✓ 3rd harmonic cavity: $\Delta f = 90\text{ Hz}$ for 2.8mm thick wall.



RF Design

Tuning cavities with overlapping modes

- First prototype TM_{110} half-cells had large freq scatter
- First cavity had π mode and $(\pi-1)$ modes totally degenerate
- Designed mode separation was very close anyway
- HFSS predicts “M” type bead pull result for 300K; linear combo of MAFIA eigensolutions similar
- At 70K, HFSS gave correct S_{21} vs. f plot, and bead pull result was flatter. Plan to try bead pull at LHe temps.





RF Design, HOMs

Higher order modes are most critical for TM_{010} cavities; for TM_{110} cavities, worst HOM is a LOM.


Rescaled from TESLA HOM couplers (J.Sekutowicz)

R/Q quantities calculated in collaboration with DESY, using both MAFIA and HFSS


HFSS 3D model used to study cavity excitation by beam as function of frequency





S parameters coupler to beam pipe)





HOM damping



HOMs excited by beam with 2mm off-set in x/y directions (HFSS)



HOM study in a chain of two copper TM_{01} cavities



F=4813 MHz. Qmax=2180, Q2=1160, Q4=890



F=4994 MHz. Qmax=26000, Q2=4990, Q4=4320

F=5474 MHz. Qmax=28300, Q2=12500, Q4=9300

Power Coupler Development

Initial design was adjustable

Plan to try a non-adjustable version with
3-stub tuner in waveguide




Nb material Control

Eddy Current Scanner donated by SNS




- ❑ Good to detect inclusions (100 μ m Ta, 10 μ m Fe, etc.), not enough for pits and scratches.
- ❑ Built disk holders for CKM and 3rd harm disks
- ❑ Upgrading to improve Scanner resolution:
 - new alignment system, new coils, etc.



Disk 3harm_b1_22_2
scanned at DESY (left) and
FNAL (right).

Size of pits \sim 50-100 μ m



Nikolay Solyak, FNAL

AAC, May 11, 2004

Cavity Manufacture



- ✓ *We purchase pure ($RRR=300$) Nb sheet from industry, and DESY has done eddy current scanning for us (planning to scan on site)*
- ✓ *Stamp on site and e-beam weld near FNAL under clean conditions*
- ✓ *RF measurements and profile measurements of $\frac{1}{2}$ cells on site*
- ✓ *We have an on-site vacuum bake facility (1000 C) to remove H_2 and anneal - have not done Titanium gettering*
- ✓ *Field flatness tuning on site*
- ✓ *BCP Acid etch has kindly been done for us by JLab, to be done in collaboration with Argonne*
- ✓ *On-site high pressure rinse with $18M\Omega H_2O$*

Also are contracting with Advanced Energy Systems to build a few cavities both types



1000°C Vacuum Oven

Production. EB welding




Welded dumbbells of
the 3rd harmonic cavity

E-beam welding
machine at Sciaky,
Chicago.



Cut weld for
inspection




Test welds on the
end-tube group.

All components (except
two flanges were e-beam
welded to specify weld
parameters.

Chemistry

**Short term: Existing
ANL facility, JLab** ➡



BCP Facility Status




M
O
C
U
P
@
F
N
A
L



- ✓ Hydraulic system - complete.
- ✓ Control system – is being tested
- ✓ Process tank – in procurement
- ✓ System readiness at FNAL – end of May
- ✓ ANL safety review and commissioning –
(need to address some issues like UPW
source, clean rooms, building mezzanine).

Cavities Produced

Eight TM_{110} mode cavities have been made, mostly shorter structures, but there is one full 13 cell prototype. One more short structure is in production, and one more 13 cell is planned




In addition to the two copper TM_{010} mode cavities shown earlier, a 3 cell has been made in niobium and a full 9 cell prototype is in production now

Recent TM₁₁₀ Cavity Production



- Cavity made with 1.6mm thick annealed Nb (top left) proved far too soft mechanically
- Made a 3 cell with 2.2mm thick Nb
- Two trial acid-etch cycles at ANL were done on the older 3 cell:
 - Restored high field levels
 - But also very high R_{SURF}
 - Bacteria in H₂O - system
 - sanitized, being retested
 - These cavities will go to JLab for etching and rinsing.
- Cold tests planned for June

Cryovessel Design & Fabrication





- ✓ LHe vessel built, assembled with 13 cell prototype;
- ✓ Magnetic shielding being annealed now
- ✓ Cryovessel design for TM_{010} / TM_{110} cavities just beginning



Cavity Production. 9-Cell Design Status

TM_{010} cavity



Cavity Production (end of Sept. 2004)

- Half-cells: done, RF measured, ready for welding
- End tubes: components 90% ready, weld tests 95% done, most fixtures are ready
- Tough schedule for e-welding




Helium Vessel and Bladetuner

- Drawings: 95% finished
- Procurement: start June
- Ready: End of 2004
- Magnetic shielding - designing

Warm Test Results TM_{010}

FNAL half-cell uniformities and f_0
very good $\sim 50\mu\text{m} \Leftrightarrow 1.5\text{MHz}$


AES half-cells $\sim 3\text{MHz}$ RMS



Field flatness before
(red) and after
tuning.

Flatness better 0.5%

Cold Test Results (TM_{110})



R_{surf} at $T=1.8K$ design goal is $110n\Omega$


Recently obtained $\sim 160n\Omega$ in TM_{110} ,
 $\sim 65n\Omega$ in TM_{010} ($\Leftrightarrow 126n\Omega$ in TM_{110})

Reason is not clear:

- > Residual beam pipe effect?
- > Power lost in coupler tip?
- > Power in weld area?
- > Otherwise wrong κ, R_{SURF} ?

Most cold tests done with 3 cell cavity -
Acid etch facilities need upgrade for 13 cell test

P_{\perp} originally $\sim 5.1MV/m$ but has decreased
to about $3.5MV/m$ with repeated tests.
Have recovered $5.4MV/m$ (but high R_{surf})
with recent acid etch





Cold Tests of the 3-cell TM_{010} cavity





Test done after 140 μm BCP, heat treatment and HPWR

Nikolay Solyak, FNAL




AAC, May 11, 2004

Cold Test of the 3-cell TM_{010} cavity (cont)



Results from the first 3-cell cavity tests


- ✓ Reached at $T=1.8K$ $R_{surf} \sim 70 \text{ n}\Omega$ ($Q \sim 4 \cdot 10^9$)
- ✓ B_{max} (mid-cell) = 110 mT $\Rightarrow E_{acc} \sim 22 \text{ MV/m}$
- ✓ B_{max} (end-cell) = 78/85 mT $\Rightarrow E_{acc} \sim 16/17 \text{ MV/m}$
- ✓ Field emission limitation (spot on the iris)
- ✓ Q (R surface) degradation vs. test#
- ✓ Plan: 20 μm BCP, HPR and repeat cold test




Quenches in short and long RF pulses

Piezoelectric R&D

We have been investigating the use of piezoelectric elements to dynamically adjust the length of the cavities in response to mechanical vibrations, temperature and pressure changes.



At 300K: Open loop resolution $O [10\text{nm}]$
 Loads $O [1000\text{N}]$
 Range of motion $O [10\mu\text{m}]$




The dynamically adjusted filter tries to match the transfer function of the piezo/cavity system; output $y(n)$ is applied so as to cancel $e(n)$.

For testing, another piezo is used to create sample microphonics

Have been able to get enough canceling amplitude at selected frequencies, but need to understand nonlinearities better

Piezoelectric R&D




Driving the cavities with sum of three sine waves at 15Hz, 27Hz, and 45Hz, where there are known mechanical resonances to the system.

RED curve is FM modulation with algorithm off
BLACK curve is FM modulation with algorithm on

Nonlinear behavior at subharmonics




Algorithm requires linear device to be emulated, but we find that if we drive at an integer fraction of the frequency of a mechanical resonance, the piezo/cavity system is non-linear. *To be investigated*



RRR measurements

RRR Measurements:


simple, very sensitive to purity, $RRR > 300$




Samples 1.6 mm:	A3	A4	A5
RRR measurement	284	310	330
U-sound pre-clean	X	X	X
100 min BCP etch	X	-	X
800°C bake	X	X	X
20 min BCP etch	-	-	X
RRR measurement	302	110	359

Microscopy Studies


Collaboration Applied Superconductivity Center/University of Wisconsin-FNAL:
Investigation of the effect of grain-boundaries on the RF surface resistance in Niobium.





SEM of BCP-etched sample, large grain in weld (left), normal (right)




Samples for inter- and intra-grain transport measurements



Grain structure in weld sample



Magneto-optical image of 5x5 mm² sample in 80 mT field (6 K)



Profilometric measurements in samples

Conclusion

Carrying out the Superconducting RF cavity R&D for these two relatively modest systems has lead us to develop a wide range of design, manufacture and test facilities that provide an excellent knowledge base for the future SCRF LINAC.