



# **He II HEAT EXCHANGER TEST UNIT FOR THE LHC INNER TRIPLET**

**Ch. Darve<sup>1</sup>, E. Blanco<sup>2</sup>, Y. Huang<sup>1</sup>, T. Nicol<sup>1</sup>, T. Peterson<sup>1</sup> and  
Rob van Weelderen<sup>2</sup>**

<sup>1</sup> Fermi National Accelerator Laboratory, Batavia, IL, 60510, USA

<sup>2</sup> CERN, European Organization for Particle Physics, Geneva, 1211, CH



**US-LHC Accelerator Project  
Brookhaven – Fermilab - Berkeley**





## *Headlines*

- ① *Overview on the LHC IR inner triplet*
- ① *IT-HXTU test description and Purpose*
- ① *Thermal measurements under investigation*
- ① *Results and discussion*
- ① *Consequences on the inner triplet*





# Overview on the LHC IR inner triplet


Eight inner triplets located @ the Interaction Regions.

C-08C-03 LHC Interaction Region Quadrupole

Cryostat Design

## Concerns:

- ☞ Large dynamic heat loads @ 1.9 K
- ☞ Require a large Heat Exchanger tube




Inner triplet heat loads - estimated				
Temperature level	50 to 75 K	4.6K	1.9K	Notes
Static heat loads (W)	220	0	18	1,2
Dynamic heat loads (W)	0	17	184	3
Total heat loads (W)	220	17	202	





## *From the LHC IR inner triplet to the IT-HXTU*

### Inner triplet



### IT-HXTU

- Four similar modules (7 m x  $\varnothing$  0.8 m) to simulate the IT cooling scheme.
- Magnet simulators (resistive heaters)
- Full He II capacity (~800 l)








## *Purpose of the IT-HXTU*

- ➡ **Validation of the the inner triplet cooling scheme by checking the max. temperature rise in the stagnant and pressurized He II.**
  - ➡ **Validation of theoretical estimation of the heat transfer in Pressurized He II.**
  - ➡ **Measurement of the heat exchanger tube wetted area.**
  - ➡ **Development of the Nonlinear Model-Based Predictive Control.**
- C-02B-03 Nonlinear Advanced Control of the LHC Inner Triplet Heat Exchanger Test Unit**






## View of the IT-HXTU





## *View of the IT-HXTU*







## *View of the IT-HXTU*



CD - July 20, 2001

**He II HEAT EXCHANGER TEST UNIT FOR THE LHC INNER TRIPLET**



## *The IT Heat Exchanger tube*



Stainless steel flange

Corrugated tube


<b>Material</b>	<b>Copper -OFHC</b>
<b>OD/ ID (mm)</b>	<b>97/86</b>
<b>Wall thickness (mm)</b>	<b>0.7</b>
<b>Corrugation depth (mm)</b>	<b>5</b>
<b>Corrugation pitch (mm)</b>	<b>12.4</b>
<b>Surface (cm<sup>2</sup>) for one side</b>	<b>416</b>
<b>Shape of the corrugated pipe</b>	<b>Helical</b>
<b>Surface treatment</b>	<b>None</b>





## Process and Instrumentation Diagram

- The heaters provide the heat load
- The JT valve controlled the saturated He II flow
- The thermal equilibrium is dictated by the evolution of the dry-out point and the overflow in the accumulator






## Instrumentation

Instrumentation	Total	Range	Accuracy
Temperature (Cernox®, Pt100)	54	1.6 – 40 K, 50 K – 300 K	$\pm 5$ mK, $\pm 5$ K
Pressure (Absolute, Differential)	5	0-1.3 bar, 0-0.13 bar, 0-7.5 mbar	0.2%, 0.03 mbar
Level (AMI)	5	0-6", 0-12", 0-28"	$\pm 2\%$ FS
Flowmeter (Turbine+RT)	2	0-20 g/s	$\pm 2\%$ FS
Heaters (Electrical resistances)	12	55, 90, 240 Watts	
Control Valves	6	0-100 %	

Temperature sensors implemented in the pressurized He II bath

- Error of  $\pm 5$  mK on the temperature measurements.
- Stainless steel tubes to route the wires.







## *Acquisition and Control system*

- ➡ Instrumentation (temperature sensor, pressure transducers, mass-flowmeter, controlled valves...)
- ➡ An industrial PLC acquires and controlled the sensors and valves.
- ➡ Profibus fieldbus routes the information to the acquisition system.
- ➡ PCVue32 is the software used for the graphic interface, controlled and acquisition
- ➡ Ethernet network permits us to acquire and supervise the equipment







## *Heat transfer in superfluid helium*

### Gorter-Mellink equation:

$$\frac{dT}{dx} = -f(T)q^m$$

with  $1/f(T)$  = thermal conductivity of He II

$$q = q_0 + \frac{Qx}{A}$$

Heat flux  
(W/cm<sup>2</sup>)

Heat flux through the  
superfluid into the  
system

If  $T=1.85$  K to  $1.95$  K @ 1 bar  
then  $1/f(T) = 1200$  W<sup>3</sup>/cm<sup>5</sup>K for  $m=3$

For estimating the temperature difference in regions with distributed heat input, we can use:

$$\Delta T = \frac{A}{(m+1)Q(1/f(T))} (q_L^{m+1} - q_0^{m+1})$$







# Heat transfer and Kapitza Effect

## Determination of the Kapitza resistance: Small scale Heat Exchanger test @ FNAL

$$R_{th} = (T_{pres} - T_{sat}) / Q_{elec}$$



$$R_{th} = 2 \cdot R_{kapitza} + R_{cu} = \alpha (1/T_{pres}^3) + b$$



$$\alpha = \frac{2}{C_{kapitza} \cdot S}$$

$$\beta = \frac{e}{S \cdot C_{cu}}$$

**R<sub>kapitza</sub>**



# Heat transfer and Kapitza Effect



	#1 - OFHC	#2 - OFHC + HCl	#3 - Bronze
<b>Characteristics</b>			
OD/ ID (mm)	97/86	97/86	123/101
Wall thickness (mm)	0.7	0.7	0.5
Corrugation depth (mm)	5	5	11
Corrugation pitch (mm)	12.4	12.4	11.7
Surface ( $\text{cm}^2$ ) for one side	416	416	978
Shape of the corrugated pipe	Helical	Helical	Bellows
Surface treatment	None	Hydrochloric acid	None
<b>Results</b>			
CKapitza ( $\text{W} \cdot \text{K}^{-4} \cdot \text{m}^{-2}$ )	893	1138	565
Kapitza conductance @ 1.85 K ( $\text{W} \cdot \text{K}^{-1} \cdot \text{cm}^{-2}$ )	0.565	0.72	0.357
Thermal conductivity @ 1.85 K ( $\text{W} \cdot \text{K}^{-1} \cdot \text{m}^{-1}$ )	88	88	2.4
Relative performance	Ref.	27%	-37%





## ***Installation & Commissioning of the IT-HXTU***

- 1. Measurement of the heat exchanger tube deflection :< 8 mm**
- 2. Installation on the supports (1.4%)**
- 3. Connecting the 4 modules**
- 4. Pressure test: 2.5 bar abs**
- 5. Leak check:  $10^{-8}$  mbar l/s (@120 mbar)**
- 6. Mechanical calibration of the controlled valves**

### **At cryogenic temperatures**


- Time constants for the thermal equilibrium: 4-6 hours**
- LHe velocity measurements: 10 cm/s**
- Controlled valves, JT valve: PID parameters**
- Recalibration of thermometers**
- Calibration of the turbine mass-flow meter**
- Calibration of the JT opening**
- Static heat load measurements**






## *Determination of the static heat loads*

👉 The static heat load was measured using the enthalpy balance between the JTvalve and the accumulator






## *Nominal condition*






# Nominal condition





## IT-HXTU Ultimate condition $Q = 315 \text{ W}$







## Comparison with calculation

DT1: from the Module 3 thermal center  
to the module end within the pressurized Helium II,  
linearly increasing heat flux  
(length=3.17 m, diameter =13.45 cm)

DT2: within the connecting pipe between modules  
within the pressurized Helium II, constant heat flux  
(length=40 cm, diameter=8.28 cm)


DT3: between connecting pipe and heat exchanger  
within the pressurized Helium II, constant heat flux  
(length=7.2 cm, diameter=8.28 cm)

DT4: within the pressurized Helium II side of  
the heat exchanger, linearly decreasing heat flux  
L=375 cm, D<sub>inner</sub>=9.6 cm, D<sub>outer</sub>=16 cm.

DT5: across the He II heat exchanger wall


DT6: due to the vapor pressure drop.

	Module 4	3	2	1
Electric power (W) =	73.13	72.54	47.19	85.90
Total electric plus static heat =	312.8 Watts			
Tsat (K) = 1.921	Average heat = 10.43 W/m			






## *DT vs. heat load - $T_{\text{sat}} \sim 1.90 \text{ K} \sim 21 \text{ mbar}$*






## *DT vs. heat load - $T_{\text{sat}} \sim 2.00 \text{ K}$ $\sim 32 \text{ mbar}$*





## Prediction for LHC high luminosity conditions

Predicted T-Tsat for HXTU at Tsat=2.007 K



## *Conclusions*

- ➡ **More than 50 heat load configurations were measured**  
[http://tspc01.fnal.gov/darve/heat\\_exchanger/instrumentation.html](http://tspc01.fnal.gov/darve/heat_exchanger/instrumentation.html)
- ➡ **Validation of the theoretical model**
- ➡ **The temperature rise at nominal LHC luminosity conditions will not exceed 50 mK.**
- ➡ **The wetted area of the heat exchanger tube is about 22 %.**
- ➡ **Increase of the connecting pipe diameter in order to reduce the temperature rise resulting from the potential LHC ultimate luminosity condition.**





## *Acknowledgement*

**This work was supported by the US Department of Energy.**

**We would like to thank the LHC/ACR, LHC/ECR, LHC/CRI groups and in particular the support of R. Losserand-Madoux, A. Bezaguet, E. Fernandez, C. Masure, B. Vullierme, L. Herblin, S. Pelletier, JB Bart, B. Beauquis, D. Tobias, M. Gautier, C. Berthelier and R. Vuillermet.**

