#### **US LHC Accelerator Research Program**

bnl - fnal- lbnl - slac

# TQC structure scale up for LQC

Fred Nobrega

LARP Long Quadrupole (LQ) Mechanical Structure Review November 28-29, 2007



#### Introduction

From 'Criteria for the Review of the LQ Magnet Structure'

5. Understanding and addressing of length scale-up issues

What are the LQC length scale-up issues?

How will they be addressed?



## LQC Scale-up Issues

#### Scale up issues:

- » Long coil handling, measuring and shimming LM
- » 4 coil handling, assembly and ground insulation
- » Coil alignment
- » Collaring and handling
- » Collared coil OD measurement and pre-stress control
- » Collared coil warm magnetic measurements
- » Yoke ID measurement
- » Collared coil shimming
- » Cold mass instrumentation
- » Skin welding LM
- » End plates welding, splicing, bullet pre-load
- » Transportation LM
- » Cold test LM


#### Legend:

plan in place

addressed understood-TQC




#### LQC Mechanical Structure




- Nitronic 40 SS collars with phosphor bronze keys
  - → initial coil preload
- SS control spacers interface with collar & yoke
  - → coil alignment
  - → yoke gap control
- Shell welding key and 12 mm thick shell
  - → remaining coil preload and alignment
- 50 mm SS end plate
  - → 14 kN total end load to coils via bullets



## LQC Instrumentation



- Voltage taps, strain gauges and RTD's.
  - → starting point is identical to TQC





## LQC In-Process Measurements


#### Same as TQC

- → Coil Cross Section Measurements (used for mid-plane shim)
- → Collar Outside Diameter Measurements (coil preload & collar-yoke shim)
- → Yoke Inside Diameter Measurements (collar-yoke shim)
- → Monitoring of Coil Strain Gauges during collaring and yoking
- → Monitoring of strain gauges on structure during shell welding
- → Monitoring of end preload gauges during and after applying end load
- → Monitoring of coil resistance during all phases of assembly
- → Hi-potting at critical steps: After collaring, yoking, end preload, and at final electricals prior to shipment to VMTF.



#### Coil Assembly

.75 mm stainless collaring protective shell (installed after coils are assembled)



• Shims and ground insulation applied to coils then placed on assembly mandrel.

- .75 mm SS collaring shell is added
- 4 coil assembly tightly wrapped with mylar film
- Process is similar to MQXB; the cold mass used in the LHCIR Q2a/b.










## LQC Collaring








LQ Mechanical Structure Review Nov 28-29, 2007

TQC structure scale up for LQC Fred Nobrega

- Coil assembly is up righted.
  The process used is similar to
  MQXB and Tevatron HGQ.
- Collar keying is done in 5-6
   passes while coil strain gauges
   are monitored
- Coil is brought to horizontal using the up right process in reverse
- Collared coil deflection is measured
  - → verify preload
  - → determine collar-yoke shim size




#### Yoke ID & Collar-Yoke Shim



TQC structure scale up for LQC Fred Nobrega



#### Yoke and Shell Welding



- The lower instrumented shell place on weld press insertion table
- Lower yoke stacks, collarcoil assembly, upper yoke stack, and shell
- Roll into press
- Prepare for welding
- Process used for TQC, LM02 (4m dipole), and MQXB.



#### Final Assembly






- Electricals
- Install bullet pressure plate
- Weld end plates
- Quadrant splice assembly
- Terminate wires to connectors
- Final electricals
- Magnetic measurements
- TEST!




## LQC Coil-Collar Alignment



• Outer pole pieces have a round notch machined into them, which will fit a round notch in the collar laminations. A G-10 tube will be placed into the notch, providing azimuthal alignment between collars and coils.




## LQC Collar - Yoke Alignment



• The collar-yoke alignment is achieved with the control spacer tab and the collar feature used for collar alignment for the MQXB.



## Yoke – Shell Alignment



- The yoke is aligned to the shell via the shell welding alignment key. This is the same technique that was used for MQXB.
- Shell welding key also used to measure cold mass twist.



#### LQ Coils

#### 1st Cured LQ Practice Coil





- Identical geometric cross section to TQ magnet
- Aluminum bronze wedges, water cut and machined end parts
- Titanium poles and Ti pole ends (keys, nose pieces)
- 1st LQ practice coil winding & curing (photos left)
- Winding of 2<sup>nd</sup> practice coil underway
- Reaction scheduled start January 3, 2008



#### LQ Coils

# Cured TQ coils ready for shipment to LBNL



1st Cured LQ Practice Coil



- Several TQ coil pairs have been wound and cured at Fermilab, reacted and impregnated at LBNL, then shipped back to FNAL.
  - This process has demonstrated that shipment of Nb<sub>3</sub>Sn coils can be routinely achieved without damage.
- The process will be repeated with BNL reacting and impregnating coils for the first LQ magnet.

TQC structure scale up for LQC Fred Nobrega



#### LQC To Do's

- Finalize coil handling & shipping tooling.
  - $\rightarrow$  cured coils
  - → potted coils
- Complete coil assembly station.
- Begin coil up-righting tooling design.
  - → vertical support structure
  - $\rightarrow$  dolly
- Procure long lead magnet parts during the 1st half of FY08.
- Procure remaining LQ magnet parts in 2<sup>nd</sup> half of FY08 as money becomes available.



#### Conclusions



- Demonstrated an understanding and have addressed length scale-up issues.
- TQ mechanical structure ready for scale-up.
- TQC structure is compatible with the LARP length scale up goals and requirements
- Structure length scale up for LQC builds on experiences from long cold masses like MQXB, LBQ, and LM01/02.
- Excellent results in first practice coil winding and curing using scale up tooling.