

**CKM, Injector III, and SRF Test Area Heat Loads and Flows**

26-Mar-02

Total (Dynamic plus Static) Heat Loads (1.8 K)				Vapor flow (g/s)		Comments
<b>CKM Station 1</b>	<b>75 K - 85 K</b>	<b>4.5 K</b>	<b>1.8 K</b>	80 K	5 K	
Warm to Cold Transition (W)	13.0	0.0	1.6			For 15 MV/sta, 8 cav (4m) gives 3.75 MV/m, while 6 cav (3m) gives 5 MV/m.8 offers redundancy.
Four 2-cavity modules total (W)	158.4	8.0	30.0			from LHC beam tube transition estimates
Supports and thermal radiation (W/m)	34.0	2.0	5.0			Scaled from SNS numbers
Dynamic RF heating (W/m)	0.0	0.0	2.1			From EES at 1.8 K surf, 5 MV/m deflection. Only 1.2 W/m if 3.75 MV/m.
Effective length of station (m)	4.0	4.0	4.0			One 13 cell cav has Lrf=0.5 m so x 8 cav=4m. Not 3m
Input couplers (W)	22.4	0.0	1.6			
HOM couplers (W)	0.0	0.0	0.0			Guesses or space fillers in red
Feed box (W)	150.0	20.0	5.0	0.0	0.0	Heat scaled from MTF Stand 4
Warm to Cold Transition (W)	13.0	0.0	1.6			
<b>TOTAL HEAT LOAD</b>	<b>334.4</b>	<b>28.0</b>	<b>38.2</b>	<b>0.0</b>	<b>0.0</b>	
Helium flow rate (g/s)	7.1	1.6	1.9			See flow summary sheet for explanation

<b>CKM Station 2</b>	<b>75 K - 85 K</b>	<b>4.5 K</b>	<b>1.8 K</b>	80 K	5 K	Same as Station 1
Warm to Cold Transition	13.0	0.0	1.6			
Four 2-cavity modules total (W)	158.4	8.0	30.0			
Supports and thermal radiation (W/m)	34.0	2.0	5.0			
Dynamic RF heating (W/m)	0.0	0.0	2.1			
Effective length of station (m)	4.0	4.0	4.0			
Input couplers (W)	22.4	0.0	1.6			
HOM couplers (W)	0.0	0.0	0.0			
Feed box (W)	150.0	20.0	5.0	0.0	0.0	Heat scaled from MTF Stand 4
Warm to Cold Transition	13.0	0.0	1.6			
<b>TOTAL HEAT LOAD</b>	<b>334.4</b>	<b>28.0</b>	<b>38.2</b>	<b>0.0</b>	<b>0.0</b>	
Helium flow rate (g/s)	7.1	1.6	1.9			

<b>TTF Module 1</b>	<b>75 K - 85 K</b>	<b>4.5 K</b>	<b>1.8 K</b>	80 K	5 K	Consider surf at 1.8 K
Warm to Cold Transition (W)	13.0	0.0	1.6			
One 8-cavity TTF cryomodule (W)	175.0	27.3	14.0			From John Weisend's presentation
Supports and thermal radiation (W)	90.0	23.0	6.0			from EES model which produced Dsgn Rport 2K conditions.
Dynamic heating (W)	85.0	4.3	8.0			Has lower Q (5e9), takes Rres=35nOhm
Feed box (W)	150.0	20.0	5.0	0.0	0.1	so residual effects significant for lower Q cavities.
Warm to Cold Transition (W)	13.0	0.0	1.6			Four pair of 100 A leads totaling 0.1 g/s per TTF Design Rept
<b>TOTAL HEAT LOAD</b>	<b>351.0</b>	<b>47.3</b>	<b>22.2</b>	<b>0.0</b>	<b>0.1</b>	
Helium flow rate (g/s)	7.5	2.6	1.1			

<b>TTF Module 2</b>	<b>75 K - 85 K</b>	<b>4.5 K</b>	<b>1.8 K</b>	80 K	5 K	Same as module 1
Warm to Cold Transition (W)	13.0	0.0	1.6			
One 8-cavity TTF cryomodule (W)	175.0	27.3	14.0			
Supports and thermal radiation (W)	90.0	23.0	6.0			
Dynamic heating (W)	85.0	4.3	8.0			

Feed box (W)	150.0	20.0	5.0
Warm to Cold Transition (W)	13.0	0.0	1.6
<b>TOTAL HEAT LOAD</b>	<b>351.0</b>	<b>47.3</b>	<b>22.2</b>
Helium flow rate (g/s)	7.5	2.6	1.1

0.0 0.1 Four pair of 100 A leads totaling 0.1 g/s per TTF Design Rept

0.0 0.1

<b>TTF 3rd Harmonic Module</b>	<b>75 K - 85 K</b>	<b>4.5 K</b>	<b>1.8 K</b>
Warm to Cold Transition (W)	13.0	0.0	1.6
One 3.9 GHz cryomodule (W)	42.5	2.4	6.0
Supports and thermal radiation (W)	34.0	2.0	5.0
Dynamic heating (W)	8.5	0.4	1.0
Feed box (W)	50.0	7.0	1.0
Warm to Cold Transition (W)	13.0	0.0	1.6
<b>TOTAL HEAT LOAD</b>	<b>118.5</b>	<b>9.4</b>	<b>10.2</b>
Helium flow rate (g/s)	2.5	0.5	0.5

80 K 5 K Same as module 1  
Use same warm to cold transition

Take one meter of CKM static loads  
Take one tenth of TESLA module

0.0 0.1 Take about 1/3 of other feedboxes

0.0 0.1

<b>Vertical Test Dewar</b>	<b>75 K - 85 K</b>	<b>4.5 K</b>	<b>2.0 K</b>
<b>TOTAL HEAT LOAD</b>	<b>180.0</b>	<b>0.0</b>	<b>20.0</b>
Helium flow rate (g/s)	3.8	0.0	1.0

Estimated based on MTF vertical dewar

Neglecting dynamic heating of test cavity

<b>Horizontal Test Dewar (Optional)</b>	<b>75 K - 85 K</b>	<b>4.5 K</b>	<b>2.0 K</b>
<b>TOTAL HEAT LOAD</b>	<b>200.0</b>	<b>20.0</b>	<b>10.0</b>
Helium flow rate (g/s)	4.3	1.1	0.5

Estimated based on horizontal test stands at MTF including end effects

Neglecting dynamic heating of test cavity

<b>Transfer lines and junction boxes</b>	<b>75 K - 85 K</b>	<b>4.5 K</b>	<b>2.0 K</b>
CKM Transfer line length [m]	125	125	125
TTF Transfer line length [m]	375	375	375
TL Supports and thermal radiation (W/m)	0.38	0.015	0.004
CKM Expansion box/anchor [number]	4	4	4
TTF Expansion box/anchor [number]	6	6	6
Exp Box Suppts and thermal rad (W/unit)	80	6.6	0.1
<b>TOTAL HEAT LOAD</b>	<b>990.0</b>	<b>73.5</b>	<b>3.0</b>
Helium flow rate (g/s)	21.2	4.1	0.2

~10"dia outer pipe, 4.5" inner 2K return.  
about same for either KTEV or MP9  
Worst case, at PC4. 281m if at LabE  
Scaled from Tev TL pipe Qto4K=0.011 W/m and Qto80K=0.19 W/m  
Worst case, at KTEV. 3 if at MP9.  
Worst case, at PC4. 3 if at LabE.  
Scaled from Tev